Technical Proposal Writing Sample

Conference Room Technology Upgrade

Portfolio Note

This sample has been sanitized for public portfolio use. Client-identifying references, security-classification references, company-identifying information, pricing, and proprietary boilerplate have been removed or generalized. The original navigation page has also been removed.

Proposal # XXXXX | Month XX, 2012

1. Introduction

[Company] is pleased to submit this technical proposal to the Client for the procurement, integration, testing, and maintenance of a video teleconference (VTC) system and conference room at a facility located in [City, State]. This proposal describes the system and the effort required for implementation, defines the scope of work, and specifies responsibilities for the task.

Our design solution is based on a review of the needs and requirements of the task and identifies the details of the proposed audio-visual (AV) solution based on room type and functionality. Government Furnished Equipment is defined as GFE.

2. Project Description

Under this project, [Company] will provide and install a complete upgraded VTC system, including new equipment integrated with an existing VTC system. [Company] will install a VTC-capable conference room and a new control room located adjacent to the conference room for operator use. Existing GFE will be relocated to the new control room and reintegrated with additional equipment supplied by [Company].

2.1 Display System

The display system will consist of a two-projector display system with 4,000-lumen brightness, 1280 x 800 native resolution, and 109-inch 16:10 ceiling-recessed motorized screens. The projectors and screens will be ceiling mounted and configured for front projection. [Company] will integrate two existing 65-inch GFE plasma displays located on the side walls with GFE SMART panel overlays. One SMART Podium will be installed in the control room.

[Company] will also provide and install three illuminated room-status signs: one outside the conference room, one inside the conference room, and one inside the VTC control room.

2.2 Switching & Distribution

[Company] will install an AMX hybrid video switcher capable of using both digital and analog signals. Distribution will be handled over category structured cabling. Images will be scaled to fit the appropriate aspect ratio and resolution of each display.

2.3 Audio System

The audio system will consist of six ceiling-mounted microphones for voice audio capture. Audio output coverage will be handled through GFE ceiling-recessed speakers integrated into the new system with a GFE amplifier. The speakers will support program audio, control-room/conference-room communication, audio teleconferencing (ATC), and VTC/remote communication.

[Company] will install an audio digital signal processor to mix audio sources and provide echo cancellation. Powered monitor speakers will be added in the control room so the operator can preview and monitor program audio.

2.4 Control System

[Company] will install a complete AMX control system consisting of two wired 10-inch AMX touch panels used for source routing of the AV system; ATC and VTC operations; display and audio sources; and room-status signage. One touch panel will be located in the control room. The second will connect to a floor-mounted raceway under the table. Control-panel functionality will be coordinated with the customer for preset and custom design specifications, and programming code will be submitted to the client upon project completion.

2.5 VTC System

[Company] will use the existing GFE codec, HD camera, and encryption devices to create a new VTC system. The VTC will connect to a GFE ISDN line. Two cameras - one GFE and one provided by [Company] - will be available to

the operator in the control room. Each camera will support conference-room monitoring and VTC use.

[Company] will use source restrictions, power controllers, and GFE encryption devices to meet client security requirements.

2.6 Infrastructure

[Company] will install a floor-mounted raceway for cable management and connection points at the conference room table. Connections will include three VGA (15-pin) inputs, three 3.5 mm audio jacks, AC power outlets, and one connection suitable for the secondary touch panel. The floor-mounted raceway will connect to the AV equipment rack in the control room.

The installation will include relocating select existing GFE rack equipment into the control room along with new equipment provided by [Company]. [Company] will integrate monitors on an existing GFE operator desk and install rack-mounted equipment in one or more floor-standing, securable equipment racks. The control room will house the primary touch panel and serve as the primary space for operation of the AV system.

3. Responsibilities

[Company] responsibilities include:

- Define installation requirements with users.
- Survey the site to determine room characteristics and recommend room layout and system configuration.
- Identify site issues that may affect cost or schedule.
- Uninstall existing AV and VTC equipment and return items that will not be reused to the Client.
- Install supplied AV equipment and GFE AV equipment.
- Set up and test the system.
- Provide an electronic documentation package.
- Provide as-built drawings, test plans, a quick user guide, and operator manuals.
- Supply specified AV equipment.
- Provide eight hours of formal training for the complete AV system.

Client responsibilities include:

- Provide access to the site for a site survey and coordinated installation activities.
- Provide sufficient space for system hardware and required furniture.
- Provide required telecommunications lines, network connections, host information, and routing information.
- Provide all equipment identified as GFE for rack integration and confirm that GFE is fully functional.
- Provide required system power and any required core drilling or cable paths.
- Provide disposal of removed equipment that is not reintegrated into the new system.
- Witness and sign off on system testing to demonstrate successful completion of the installation.

4. Assumptions & Clarifications

- [Company] personnel will perform a site survey immediately after award.
- On-site work will be performed during normal business hours, Monday-Friday, 7:30 a.m.-5:30 p.m.

- GFE PCs should be configured to the recommended display resolution when possible; alternate supported resolutions will be documented as needed.
- All materials specified as GFE are assumed to be in good working order.
- If additional video connectivity is required at the conference-room table, additional equipment may be required.
- HDMI and USB communication through hubs, extenders, sources, and displays can occasionally produce interoperability anomalies beyond the AV integrator's control.
- A clear cable path is assumed from the control-room rack to required AV equipment.
- Mounting structures are assumed to support the specified equipment loads and to be free from mechanical vibration.
- The installed system will be HDCP compliant; protected digital content may be subject to source and display key limitations.

5. Schedule

[Proprietary boilerplate omitted from public writing sample.]

6. Warranties and Service Plan

[Proprietary boilerplate omitted from public writing sample.]

7. Cost Information

[Proprietary boilerplate omitted from public writing sample.]

8. Terms & Conditions

[Proprietary boilerplate omitted from public writing sample.]

9. Company Profile

[Proprietary boilerplate omitted from public writing sample.]

10. Project Management & Implementation

[Proprietary boilerplate omitted from public writing sample.]

11. Conclusion

[Proprietary boilerplate omitted from public writing sample.]